1 PROPOSED GROUND FLOOR PLAN (EAST)
A2.03 / 1 : 50

FLOOR TYPE B (FL2) -
DALTILE SADDLEBROOK XT 150x900mm
'GRAVEL ROAD' - STACKED BOND PATTERN

FLOOR TYPE A (FL1) -
DALTILE SADDLEBRROK XT 150x900mm
FARMHOUSE - RUNNING BOND PATTERN of 3/4 STAGGER

3 SILICON MOVEMENT JOINT DETAIL
A2.03 / 1 : 20

Montgomery Sisam Architects Inc.

197 Spadina Avenue, Toronto, Ontario M5T 2C8 montgomerysisam.com
Tel 416.364.8079 Fax 416.364.7723

MontgomerySisam

FLOORING LEGEND

- NEW STANDARD TILE FLOORING (SADDLEBROOK XT : 150mm X 900mm)
- NEW TILE FLOORING AT TERMINATION (SADDLEBROOK XT TILE: 300mm X 600mm)
- EXISTING FLOORING TO REMAIN AS-IS

KEYNOTE LEGEND

1 OVERNIGHT WORK. CONTRACTOR TO PHASE HOARDING TO PROVIDE LIGHT TRAFFIC ONLY FOR MIN. 7 DAYS AFTER TILE INSTALL. REFER TO SPECIFICATIONS

FLOOR & WALL FINISH LEGEND

MOVEMENT JOINT LOCATIONS — MJ
SILICON MOVEMENT JOINT LOCATIONS — SMJ
WHITE BRICK STAIN

NOTES:
MOVEMENT JOINT GUIDELINES -
INTERIOR: 16'-20 ft. EACH DIRECTION
EXTERIOR: 8'-12 ft. EACH DIRECTION

DEMOLITION & CONSTRUCTION NOTES

TEMPORARILY REMOVE ALL FURNITURE AND EQUIPMENT THAT ARE IN CONFLICT WITH THE CONSTRUCTION WORK. STORAGE LOCATION TO BE COORDINATED WITH BUILDING MAINTENANCE DEPARTMENT.

REMOVE EXISTING FLOOR FINISH AS REQUIRED TO ACCOMDATE NEW TILE SCOPE PER OUTLINE INDICATED ON DRAWING. PREPARE SUBSTRATE FOR NEW FLOOR FINISH.

REMOVE AND RELOCATE EXISTING LIGHT FIXTURES THAT ARE IN CONFLICT WITH THE CONSTRUCTION WORK. STORAGE LOCATION TO BE COORDINATED WITH BUILDING MAINTENANCE DEPARTMENT.

PROVIDE HOARDING DURING CONSTRUCTION AS NOTED IN DRAWINGS:
(92mm METAL STUD AND TYPE "X" GWB SHEATHING)
PROVIDE NEGATIVE PRESSURE VENTED TO EXTERIOR
PATCH AND MAKE GOOD ANY IMPACT DUE TO VENTING AND HOARDING

PROVIDE BULLNOSE BASE TILE SIMILAR TO FLOORING TILE AT ALL PROPOSED LOCATIONS OF NEW FLOOR AT EXISTING WALL. REFER TO SPECIFICATIONS.

FOR MINIMUM SETTING TIME OF TILE BEFORE EXPOSURE TO HEAVY TRAFFIC REFER TO MANUFACTURERS SPECIFICATION.

PROVIDE NEW FLOORING AS PER DRAWINGS. PREPARE SUBSTRATE AS PER MANUFACTURER'S INSTRUCTIONS

#	date:	revision:	by:
4	23-05-18	ISSUED FOR ADDENDUM 004	MSA
3	23-04-18	RE-ISSUED FOR TENDER-R01	MSA
2	22-12-23	ISSUED FOR TENDER	MSA
1	22-12-02	ISSUED FOR REVIEW	MSA

revisions

-GROUND FLOOR

All drawing and specifications are the property of the architect. The contractor shall verify all dimensions and information on site and report any discrepancy to architect before proceeding.

LAKESHORE LODGE - QUIET RM, LOBBY AND GIFTSHOP RM RENOVATION

3197 LAKE SHORE BLD W, ETOBICOKE,
ON M8V 3X5

PROPOSED FLOOR PLAN

scale:	As indicated
drawn by:	MO
reviewed by:	AR
job number:	21508.F04
plot date:	2023-01-16

drawing number:

A2.03

2023-05-18 10:09:18 AM C:\Users\asimagir\Documents\21500 F99-014 Quiet Room Infill-New_asimagir@montgomerysisam.com.rvt