

2023-T-117 - City of Niagara Falls GO/VIA Station – Interior Alterations and Upgrades

Date Issued: Thursday, March 28th, 2024

Addendum No. 6

No. of Addenda pages: 3

Attachments: Not applicable.

Revisions

Revision 1: Part 1 – Invitation and Submission Instructions

1.6 RFQ Timetable, 1.6.1. Key Dates is revised as follows:

Issue Date of RFT	Tuesday, February 20 th , 2024
Site Visit / Pre-Bid Meeting	Thursday, February 29 th , 2024 at 11:00 AM local time
Deadline for Questions	Wednesday, April 3 rd , 2024 at 12:00 PM local time
Deadline for Issuing Addenda	Tuesday, April 9 th , 2024
Submission Deadline	Tuesday, April 16 th , 2024 at 2:00 PM local time
Anticipated Execution of Contract	May 2024
Irrevocability Period	Ninety (90) calendar days

Revision 2: Appendix D - NF Station Tender Drawings (Revised), A/1000

Delete –

If the existing is 75mm and reconnect. Provide the cost of this replacement separately in bid.

Replace with –

Contractor to site scan for buried drain pipe and is to assume replacement to a 100mm size with required connections; if the existing pipe is confirmed to be 100mm

already and in good functioning order; a credit for the supply and installation shall be provided back to the Region.

Questions and Answers

Question 1:

1/M005 states “CONTRACTOR TO SITE SCAN FOR THE BURIED DRAIN PIPE SIZE. REPLACE DRAIN PIPE TO 100mm IF THE EXISTING IS 75mm AND RECONNECT. PROVIDE THE COST OF THIS REPLACEMENT SEPARATELY IN BID.”. Please advise where this cost is to go in the bid submission.

Answer 1:

Refer to Revision 2.

Question 2:

Detail 6/A1000 shows exterior sidewalk at 6” thick, Detail 6/A503 shows 200mm concrete with 200mm of granular base, Please clarify thickness and if new granular is required.

Answer 2:

Detail 6/A1000 shows the walkway lined with brick works. Please follow Detail 6/A503 for site work detail. This work is to be included in Provisional Item #1.

Question 3:

Is any Mechanical work in Room 114 to be included in base bid? Note 2 on M-0007 states work in 114 and 115 is NIC, Please clarify if these are part of a provisional price.

Answer 3:

There are no provisional items related to Mechanical for rooms 114 &115. Any mechanical works in rooms 114 & 115 as shown or indicated within the tender drawings/specifications, to be included in the base bid.

Question 4:

Is any Electrical work in Room 114 to be included in base bid? Note 11 on E-0001 states work in 114 is NIC, Please clarify if this is part of a provisional price.

Answer 4:

There are no provisional items related to Electrical for rooms 114 & 115. Any electrical works in rooms 114 & 115 as shown or indicated within the tender drawings/specifications, to be included in the base bid.

Question 5:

Please clarify thickness of HDPL that is required for W8 and C3 , is the intent to have 0.7mm HDPL as per Div 06 20 00 2.7.2.1.2 on a MDF substrate to make the 10mm thick panel? Please provide product spec c/w corresponding rail system.

Answer 5:

Pre-manufactured panel system including mounting hardware and accessories with concealed surface. Panel finish: 0.7mm HDPL as per Div 06 20 00

Question 6:

On the plumbing drawings drainage plans it states, " provide separate price if drain size is not a 100 mm pipe". I don't see a place to enter that value on the submission forms in the system.

Answer 6:

Refer to Answer 1.

End of Addenda