

Addendum 3

Request for Quotation

RFQMA24 – 5030

Glenforest Secondary School City of Mississauga

Pool Demolition

TO: ALL POTENTIAL BIDDERS

This Addendum 3 has been issued for the above-mentioned RFQ.

- Please note that the closing date has been extended to May 24, 2024, at 4 p.m. local time.
- Please see attached Addendum No. 3 from architect.

All other terms and conditions shall remain the same.

Regards,

John Marinescu, Commodity Specialist
Peel District School Board
Tel. (905) 890.1010 x 2123
Fax. (905) 890-0660
E-mail: john.marinescu@peelsb.com



etude architects inc.

t 416.226.5779

30Kern Road, Suite 106

f 416.226.9844

Toronto ON Canada M3B 1T1

info@etudearchitects.com

www.etudearchitects.com

Project No.: ITTMA24-5030

Addendum No. 3

Page 1 of 1

Date: May 16, 2024

Project: Glenforest SS – Pool Demolition

The following information supplements and/or supersedes the bid documents issued on April 23, 2024.

This Addendum forms part of the contract documents and is to be read, interpreted, and coordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject bidder to disqualification.

1. Intent:

- 1.1. This Addendum is issued to clarify the Procurement Requirements, Specification, Architectural Structural and Electrical Scope of work.

2. General:

- 2.1. Refer to Mechanical & Electrical Addendum #2:

End of Addendum No.3

**MECHANICAL & ELECTRICAL ADDENDUM #2
GLENFOREST SECONDARY SCHOOL
POOL DEMOLITION
2575 FIELDGATE DRIVE, MISSISSAUGA, ONTARIO. L4X 2J6
MAY 16, 2024**

The following document is hereby made a part of the Contract Documents.

The following revisions and/or additions shall be made to Drawings and/or specifications and the cost shall be included in Tender Price.

General:

1. The General Contractor is responsible for retaining the services of an experienced Irrigation Contractor for all work associated with the Irrigation System (including, but not limited to, the relocation of the Controller and the new irrigation line to the existing valve box). All new piping shall be of polyethylene type.

Drawing M5 – Demolition Plans:

1. Note #4 – Including for extending of the existing control wiring serving the Irrigation Valve box at the location of Note #4 from the valve box to the new Controller Location in Gym Storage (169C). Relocate the existing water meter and control valve upstream of the irrigation line exiting the building to the new permanent location in Gym Storage (169C).
2. For all services removed in the area of demolition, cap all piping as far upstream as possible after demolition of all redundant lengths of piping. As per the Archives, the pool was serviced with a new 4” domestic cold water line, 2” domestic hot water line, ¾” domestic hot water recirculation line and 2-1/2” fire line from the existing School. Remove and cap the cold water and fire line back to the Water Meter in Custodial Storage (164B). Remove and cap the hot water and recirculation line back to the take-offs in the Boiler Room.

Drawing M6 – Demolition Plans:

1. For the two (2) rooftop units located on the Low Roof being demolished, the rooftop units shall be removed and disposed of off site by the Mechanical Contractor. Remove the associated redundant portion of gas piping serving the units (approximately 180’ in length running on the roof).
2. For all services removed in the area of demolition, cap all piping as far upstream as possible after demolition of all redundant lengths of piping.

Drawing M7 – Site Servicing Demolition Plans:

1. Cut and cap the 6” buried sanitary forced drain at both ends (at the Pool Building Perimeter and at the manhole).
2. Cut and cap the 10” storm at the manhole as well.

END OF ADDENDUM #2