

July 08, 2024,

Sent via Email (2 pages)

**ADDENDUMNO. 1
RFTWORK ASSIGNMENT NO. CREM-PMO-24-009
IN ACCORDANCE WITH
REQUEST FOR SUPPLIER QUALIFICATION (RFSQ) NO. Doc 3512316731
Closing July 15, 2024**

Structural Rehabilitation of the East Entrance at 703 Don Mills Rd. facility as detailed in the consultant's Drawings and Specifications documents and according to the City's Contract.

CLOSING DATE: July 15, 2024 AT 12:00 P.M. (LOCAL TORONTO TIME)

Deadline for Questions July 9, 2024 AT 12:00 P.M. (LOCAL TORONTO TIME)

Please refer to the above Request for Quotation (RFQ) document in your possession and be advised of the following:

I. **QUESTIONS/ CLARIFICATIONS:**

- 1) **Question 1:** The quantity or the area where are tactile plates and what kind of plates(spec)? Please clarify.

Answer 1: Drawing 1/R100 shows the tactile plate locations and Specification Section 01 11 13, Clause 1.4.23.1 indicates:

.23 New Tactile Plates

- .1 Provide all labour, equipment, materials and supervision required to supply and install new tactile plates at top of stair risers as indicated in the Project Drawings and Specifications.

Product: 24" Wide Armor-Tile Tactile System by Kinesik (Surface Applied) to span full width of stairs

Contractor to seal all penetrations prior to anchoring.

- 2) **Question 2:** The Stainless-Steel Handrails – please provide the quantity.

Answer 2: Drawing 1/R100 shows the new handrail locations in plan. Contractor to site verify dimension to determine lengths.

- 3) **Question 3:** Please clarify the Mechanical scope of work, if it is any?

Answer 3: The mechanical and electrical scope consists of all mechanical and electrical work needed to facilitate the structural repairs. This may include temporary relocation, diversion, support, etc., of the services below. This will be paid through the allowances, using base building Contractors. Please see Specification Section 01 11 13, Clause 1.4.25.1.

It is important to note that, during the entire course of construction, protection of equipment in the space below the area of work must be provided and be included in the base cost of the bid.

The required protection includes:

- proper covering of equipment from construction dust and debris with plywood panels or heavy-duty tarp,
- daily clean-up/vacuuming and
- cover of fire alarm detection devices as necessary to prevent false alarm during active construction with provision for fire watch. Remove the cover when workers are not present and fire watch not provided.

Should you have any questions regarding this addendum, please contact the Roster Captain named below.

Please attach this addendum to your call document and be governed accordingly. Suppliers must acknowledge receipt of all addenda in their submission in the space provided on the Bid Form as per Clause 1.10 in Part 2 – Form of Agreements **(RFSQ) NO. Doc 3512316731**. All other aspects of the call remain the same.

END OF ADDENDUM NO. 1

Roster Captain Name: Malake AbouHmaid,
Title: Sr. Project Manager, Project Management Office,
Division: CREM