

August 9, 2024

Posted via Ariba
(3 pages)

**ADDENDUM No. 3
REQUEST FOR TENDER No. Doc4608319077**

REVISED SUBMISSION DEADLINE: 12:00 NOON (LOCAL TIME), AUGUST 20, 2024

FOR: BENDALE ACRES EMERGENCY POWER INSTALLATION

Please refer to the above Request for Tender document in your possession and be advised of the following:

I. QUESTIONS AND ANSWERS

Q1. Is Drawing E5-01 item #2, you are asking for separate price not in the tender form.

A1. As per the note 2 in DWG E5-01, this connection is not a part of this contract. Information is provided as a reference for future work - separate price is not required.

Q2. What is the size and Dimensions of Concrete bases?

A2. Concrete housekeeping pad is 4" in height and extends 4" past the front and side edges around the equipment.

Q3. Where is the area of work of Masonry & Finish Carpentry.

A3. Any Masonry or Finish Carpentry work, if required, is the cutting, patching & paint touch up work to facilitate the electrical work. Contractor shall validate the locations based on mandatory site review conditions.

Q4. Regarding 15% General Requirement. Where we have to include this item in the pricing form. Is this to be included by us in the contract or you will added after we submit the tender. Please add a fixed number instead of this.

A4. The 15% General Requirements calculation will be inclusive of the Supplier's TOTAL BASE BID PRICE (refer to Line Item 5.2) and will be automatically calculated in SAP Ariba.

Q5. Is there any Metal work in the contract?

A5. The supplier to clarify/define what kind of Metal work they refer to.

Q6. Please confirm the working hours of the project.

A6. Please refer to **Hours of Work** in 21501.F03_BA-Power Upgrade Operational Plan.docx issued with Addendum No.1.

Q7. Please confirm who the base building BAS contractor is.

A7. Please refer to C6. Base Building Contractor list in the Addendum No.1.

Q8. Regarding the Vitalink Cable – Is a separate bond wire required to be installed along side the cable or is the copper sheath acceptable for this purpose?

A8. The copper sheathing can be used as a bond as defined by the manufacturer. If current rating is above the manufacturer's recommendation, then a separate bond wire is required.

Q9. Regarding the Vitalink Cable – Is this cable to have a PVC jacket or is the copper sheath without the coating acceptable?

A9. PVC jacket is not required unless the contractor decides to run any feeders outdoors.

Q10. Switchboard A1 calls for 2 DMS. Are these to be integral to the switchboard or can they be exterior mounted?

A10. Both integral and exterior mounted metering systems are acceptable.

Q11. Drawing 5.01 and 5.02 have notes about work that is “Not part of this contract” and makes mention of Drawing 5.15 and a Separate Price. Can you please confirm if this is as part of the work or not?

A11. These items are not part of the work – no separate price is required. Refer to Q1-A1 in the Addendum No.3.

Q12. It was mentioned at the site visit that the panels in the Upper Penthouse can be mounted off the wall to remove the need for relocating the BAS Work. Please confirm that this is accurate and that BAS work is no longer required.

A12. Yes, BAS and conduit rework is not required as long as Contractor provides floor mounted panels or provides a surface in front of the existing conduit that a panel can be safely mounted on.

Q13. Please confirm that all work, including power shutdowns, can be performed during the day. If all power shutdowns need to be performed after hours please advise so that all bidders can quote accordingly.

A13. All work is anticipated to be performed during normal business/working hours. Based on previous projects experience, we anticipate the power shutdowns will be minimal and can be coordinated within normal business hours. However, the number and duration of the power shutdowns will depend on Contractor's means and measures, which shall be communicated with and get approval from Home (BA) 48 hours prior to any shutdowns.

Q14. Please confirm working hours as well as shutdown requirements/hours.

A14. Please refer to Q6-A6 in Addendum #3 for working hours; refer to Q13-A13 in Addendum #3 for shutdown requirements/hours.

Please note: If you have previously submitted your bid before the release of this addendum, you will be required to resubmit your bid in SAP Ariba.

Should you have any questions regarding this addendum send via the event message board or contact Alexandra Mutinelli-Djukic at Alexandra.Mutinelli-Djukic@toronto.ca.

Suppliers must acknowledge receipt of all addenda in the space provided on Part 4 – Submission Form as per Part 1 Tender Process, Section 1 RFT Specific Process and Submission Instructions, Item 1.7 – Addenda, of the Tender document. All other aspects of the Tender remain the same.

Yours truly,

Aimee Yang, Supervisor
Community and Social Services and City Manager's Office
Purchasing Client Services
Purchasing & Materials Management Division