# City of Woodstock

## THE CORPORATION OF THE CITY OF WOODSTOCK Engineering Department

944 James Street

Woodstock, ON N4S 0B5 Telephone: 519-539-1291

Tuesday, August 13, 2024

# PUBLIC WORKS ADDITION & RENOVATION CONTRACT NO. ENG2024-11191

### Addendum No. 3

The following addendum is to be read in conjunction with, and form an integral part of the tender and contract documents. Acknowledgement of receiving the addendum will be made on line in the appropriate area.

It is the responsibility of the Prime Contractor to ensure all parties submitting bids are aware of this addendum and its contents.

#### Question #1

Please provide specifications for the chair rails in the lunchroom 111.

#### Answer #1

See section 5 on A3.3 for chair rail detail.

#### Question #2

Please provide specification for all the washroom accessories missing: M1 & M2 Mirrors, 4 type grab bars, safety coat hook, shower curtain, curtain rod, shower seat BR1 & BR2.

#### Answer #2

GC to source and provide submittals for approval.

#### Question #3

Please confirm if there are any Sanitary Napkin and Waste Receptacle Vendor.

#### Answer#3

Frost was used in the previous additions.

#### Question #4

Please provide specification for urinal screens.

#### Answer#4

GC to source and provide submittals for approval. Reference Bobrick classic series.

#### **Question #5**

Please confirm there is no wall base where we do concrete sealer.

#### Answer#5

Wall base is located anywhere there is gypsum board.

#### **Question #6**

Referencing A 1.4: at grid A and Between Grid 12 & 5 a new parapet will be built and it mentioned to match existing membrane at flashing area. Please provide the existing roof assembly of the existing roof.

#### Answer#6

Refer to Addendum#1, answer#8.

#### Question #7

In the footing schedule F1, F2, F3 & F4, types of footings shown, but at plan only F1 type seen, please advise.

#### Answer#7

This is a standard footing schedule, F1 & F4 are shown on G2.1, the F4 footing is located at gridline A.1/6.1. F2 & F3 have been deleted from the schedule.

#### **Question #8**

Referencing 03 35 50: Please confirm if Hardness & sealer Euco Diamond is required for the new SOG

#### Answer#8

Refer to room finish schedule, no hardener & sealer required under VCT.

#### **Question #9**

Please clarify if GC will supply and install the washer & dryer, GC to install.

#### Answer#9

Owner will supply washer and dryer.

#### Question #10

Specification calls for 20MPA block, but structural drawings call for 15MPA. please clarify Is there a core fill schedule?

#### Answer#10

15MPA block is acceptable.

#### Question #11

Are there electrical panel schedules available?

#### Answer#11

There is no electrical schedule available, breakers and circuits will need to be confirmed on site.

#### Question #12

On Drawing E0.2 there is no feeder schedule. Can the engineer provide the size of conduit/wire they prefer to use on this project? Also which feeders are expected to be reused?

#### Answer#12

Refer to electrical drawings for which panels are to be replaced. Reuse existing wires and conduit if possible. Electrical subcontractors to determine size of conduit/wire if required.

#### **Additional Comment:**

Refer to room finish schedule, room 112 wall material should be Concrete Block/Gypsum.

Closing date for this bid will remain as August 27, 2024.

Additional drawings sections added for bulkhead and column in existing locker room, refer to attached drawing sheets.


#### **Attachments:**


21367MAIN17-D1.1 - Ground Floor Demolition Plan 21367MAIN17-D3.2 - Demolition Sections 21367MAIN17-A1.5 - Reflective Ceiling Plan 21367MAIN17-A3.6 - Sections and Details


Craig Wallace
Manager of Building & Facilities/CBO


CW/tg/


**END OF ADDENDUM** 



























**ISSUED FOR** 

PRELIMINARY



2024-08-2

DATE

24×36

A3.6

DESCRIPTION

CHECKED

JΗ

AS NOTED

PROJECT NUMBER

FILE NAME

21367

21367MAIN17

NORTH ARROW

CLIENT REVIEW SITE PLAN APPROVAL BUILDING PERMIT ■ TENDER ADD SECTION 21 □ CONSTRUCTION DATE 2024-07-24 REV. BYDRAWN This drawing is the property of CITY OF WOODSTOCK **ADDITION** 485037 SWEABURG ROAD SPH ENGINEERING INC. SPH Engineering Inc. and is not to AAWOODSTOCK, ONTARIO ENGINEERING BLDG SECTIONS AND DETAILS AND be copied or distributed for any REAL WORLD ENGINEERING SOLUTIONS reason or by any means without 944 JAMES ST RENOVATION TEL: 519-539-5700 FA.1: 519-539-5775 2022-07-12 the permission of the owner.