

Date Issued: October 15,2024

C13-20-24 - General Contractor required for Macassa Lodge Space and Domestic Hot Water (DHW) Heating Boilers Upgrade

ADDENDUM 4

1. CLOSING DATE EXTENSION

The closing date has been extended from October 16, 2024 to Friday, October 18, 2024 at 3:00 PM (Hamilton time).

2. <u>REVISIONS</u>

1. Addendum 3, R4

Delete Addendum 3, R4 entirely.

Add: "

R4: The existing vent is approximately 1000mm in diameter. The details on the size and method of installation are as follows:

- 1. Existing vent is supported from each floor slab. Please remove the block walls in the laundry and garbage chute rooms as required to access and remove the existing supports.
- 2. Reinstate the walls to original condition and paint walls to match existing once new vents are installed.
- 3. Install space heating boilers as shown on drawing M-4 to ensure there is not more than one 90-degree elbow when venting transitions from vertical to horizontal.
- 4. Slope venting as shown and provide additional drains every 10 meter as required. See drawings M-11 & M-12 for elevation views.
- 5. Submit venting shop drawings for engineer's review. "

2. Appendix A Specifications and Drawings, Drawing Number M-4

Delete Appendix A Specifications and Drawings, Drawing Number M-4 entirely.

Add: "Revised - Addendum 4 -Drawing Number M-4."

C13-20-24 Addendum 4 Page 1 of 2
General Contractor required for Macassa Lodge Space and Domestic Hot Water (DHW) Heating Boilers

3. ADDITION

1. Appendix A, Specifications and Drawings

Add the following: "Drawings Number M-11 and M-12"

END OF ADDENDUM





