



**Addendum #1**  
**T24-45 - Staffroom & Workroom Alterations at Dunbarton H.S.**  
**South Campus**  
**Closing Date: Thursday, December 5, 2024 before 11:00 AM**

---

**Question 1:**

Please confirm the deck height?

**Answer 1:**

The metal deck height is 11'-8" from the finished floor.

**Question 2:**

-Can you provide the designated substance report.

-Is there any asbestos removal.

**Answer 2:**

-Please see the attached DSR prepared by Parasol Environmental.  
(13188 Dunbarton HS (South Campus), 20240209, Limited DSUB Report.pdf)

-No asbestos removal for the project.

**Question 3:**

Will the amount of data drops be reduced as mentioned during the mandatory site meeting.

**Answer 3:**

Yes, Refer to the attached revised electrical drawing E101. (T24-45 Addendum #1 - Dunbarton HS South - Prep Room Alterations - E101\_27 Nov 2024.pdf )

Note: Relocated data is in a revision bubble on Demolition Plan & Proposed plan and new junction boxes are in red text with a yellow highlight.

**Revised scope of work :**

Delete x30 new data

Relocate x1 existing data

Add x8 new empty junction boxes complete with face plate, EMT in wall to above ceiling, with pull string.

**Question 4:**

Can you provide the lintel detail for the new washroom door openings.

**Answer 4:**

Please refer the attached structural drawing by Engineering Link.

End of Addendum #1