

HARDWARE SCHEDULE

PROJECT NAME: DSS - UOFT SCARBOROUGH - SABREE LAB RENOVATION

HARDWARE SETS

SET: 1.0

DOORS: [SW247](#)

DESCRIPTION: CARD READER SEALS

1	CONTINUOUS HINGE W/ POWER TRANSFER	CFM_SLF-HD1 EL-CEPT X DOOR HEIGHT		PE
1	FAIL SECURE LOCK	LX LC RX 8271-24V LNJ	US32D	SA
1	CYLINDER C/W CMK & GMK	TO MATCH EXISTING OWNERS STANDARDS C/W CAM AS REQ'D		OT
1	CONC OVERHEAD STOP	1ADJ-436	689	RF
1	SURFACE CLOSER	4040XP .RWPA MOUNT ON CORRIDOR SIDE	.689	LC
1	KICKPLATE	GSH80 200MM X 50MM LDW MS	C32D	GA
1	PERIMETER SEAL SET	PEMKOSTCSET-4B X OPENING WIDTH X HEIGHT	BL	PE
1	PERIMETER GASKETING	2891CV X 1/WIDTH + 2/HEIGHT		PE
1	AUTO DOOR BOTTOM	434ANBL X DOOR WIDTH		PE
1	ELECTROLYNX HARNESS	QC-C1500		MK
1	ELECTROLYNX HARNESS	QC-C306		MK
1	CARD READER	BY SECURITY CONTRACTOR		OT
1	DOOR CONTACT	BY SECURITY CONTRACTOR		OT
1	CENTRALIZED POWER SUPPLY	BY SECURITY CONTRACTOR		OT
1	ELECTRIFIED HARDWARE ELEVATION	BY CONTRACTOR		OT

NOTES: DOOR IS NORMALLY CLOSED AND SECURED.

PRESENT AN AUTHORIZED CREDENTIAL TO THE CARD READER TO GAIN ACCESS.

UPON FIRE ALARM ACTIVATION OR POWER FAILURE, THE DOOR WILL BE CLOSED AND SECURED.

EMERGENCY KEY OVERRIDE. FREE EGRESS AT ALL TIMES.

STC SET INCLUDED THRESHOLD AND SEALS.

REUSE THE EXISTING DOOR, CHECK IF DOOR IS IN WORKING CONDITIONS BEFORE PERFORMING ANY HARDWARE INSTALLATION.

SET: 2.0

DOORS: [SW545](#), [SW546](#)

DESCRIPTION: CARD READER SEALS 45MIN FR

1	CONTINUOUS HINGE W/ POWER TRANSFER	CFM_SLF-HD1 EL-CEPT X DOOR HEIGHT		PE
1	FAIL SECURE LOCK	LX LC RX 8271-24V LNJ	US32D	SA
1	CYLINDER C/W CMK & GMK	TO MATCH EXISTING OWNERS STANDARDS C/W CAM AS REQ'D		OT
1	CONC OVERHEAD STOP	1ADJ-436	689	RF
1	SURFACE CLOSER	4040XP .RWPA MOUNT ON CORRIDOR SIDE	.689	LC
1	KICKPLATE	GSH80 200MM X 50MM LDW MS	C32D	GA
1	PERIMETER SEAL SET	PEMKOSTCSET-4B X OPENING WIDTH X HEIGHT	BL	PE
1	PERIMETER GASKETING	2891CV X 1/WIDTH + 2/HEIGHT		PE
1	AUTO DOOR BOTTOM	434ANBL X DOOR WIDTH		PE
1	ELECTROLYNX HARNESS	QC-C1500		MK
1	ELECTROLYNX HARNESS	QC-C306		MK
1	CARD READER	BY SECURITY CONTRACTOR		OT
1	DOOR CONTACT	BY SECURITY CONTRACTOR		OT
1	CENTRALIZED POWER SUPPLY	BY SECURITY CONTRACTOR		OT
1	ELECTRIFIED HARDWARE ELEVATION	BY CONTRACTOR		OT

NOTES: DOOR IS NORMALLY CLOSED AND SECURED.

PRESENT AN AUTHORIZED CREDENTIAL TO THE CARD READER TO GAIN ACCESS.

UPON FIRE ALARM ACTIVATION OR POWER FAILURE, THE DOOR WILL BE CLOSED AND SECURED.

EMERGENCY KEY OVERRIDE. FREE EGRESS AT ALL TIMES.

STC SET INCLUDED THRESHOLD AND SEALS.

NEW FIRE RATED OPENING. REMOVE EXISTING DOOR AND FRAME.